ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Dated 27th January 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. of 10th February 1930, for the construction of a Building for the Guard Room Bell of Arms and office of the Special Reserve lines on Mysore Road, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3A. Tenders quotating percentages below or above estimate will not be received.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for construction of a building for the Guard Room, Bell of Arms and Office of the Special Reserve lines on Mysore Road, Bangalore" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Abstract quantities for constructing a new Guard Room, Bill of Arms, etc., in the Special Reserve Police lines, Bangalore.

Sl. No.	Items of work	Unit	Quantity	Rate
1	Blasting Trap boulders over surface ...	L. S.	Rupees	
2	Earthwork excavation foundation and filling in basement with consolidation, etc.	C.yd.	127	
3	Benching rock 3" deep wherever necessary in the foundation.	L. S.	Rupees	
4	Filling foundation with burnt stone jelly concrete in mortar.	C.ft.	894	
5	Filling foundation with burnt stone in clay ...	"	2,448	
6	Burnt brick in clay up to 25' to high ...	"	4,853	
7	Burnt brick in mortar up to 25' high ...	"	1,166	
8	Burnt stone slabs 5" thick roughly dressed ..	S.ft.	838	
9	Teakwood panel doors with rectangular glassed ventilators including iron fittings and 1½" thick plank.	"	253	
10	Teakwood panel windows with rectangular glassed ventilators outside panel shutter and inside glassed shutters with ¾" iron bars and iron fittings, etc., and 1" thick plank.	"	398	
11	Teakwood work wrought and put up with wood oiling, etc.	C.ft.	244·13	
12	Steel girders with painting, etc.	C.wt.	24½	
13	Roofing with pucca terrace 9' thick	Sqr.	15·69	
14	Roofing with 1st class Mangalore tiles on 2"×1" teak reepers and 25' high.	"	15 30	
15	Ridge tiles set in mortar plain	R.ft.	107	
16	Teak plank to valley	"	28	
17	Cement fillet to valley	"	28	
18	Cornice 9"×9"	"	375	
19	Parapet wall 2' high	"	16	
20	Teakwood finials	Each	4	
21	Sham circular ventilators	"	4	
22	Ornamental iron railings 3' high	R.ft.	16	

L. No.	Items of works	Unit	Quantity	Rate
23	Plastering with mortar	Sqr.	95·83	
24	White and colour washing 2 coats	"	95 83	
25	Flooring with granite slabs on 3 " concrete bed and cement pointing, etc.	"	10·56	
26	Flooring with 1½ " thick cuddapah slabs on 3" concrete bed and cement pointing.	"	2·51	
27	Flooring with 1st class Mangalore clay tiles 9" x 9" Sqr. set in mortar and cement pointing.	"	9·14	
28	Chocolate painting 3 coats	"	16·73	
29	Cement pointing	"	3·12	
30	Binding wall over gable	R.ft.	71	
31	Turring to wood work	Sqr.	5·00	
32	Stair case 14 feet high	L. S.	Rupees	
33	Screen wall of asbestos sheets with teak frame with painting, etc., complete.	No.	2	

Dated 18th January 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 8th February 1930, for constructing a slabbed tunnel of 5 vents of 5' x 6' in place of damaged masonry arched culvert in 3—10 of Bangalore-Bellary Road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3(a) Tenders quoting percentages below or above estimate will not be received.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a slabbed tunnel of 5 vents of 5' x 6' in place of damaged masonry arched culvert in 3—10 Bangalore-Bellary Road in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Slabbed tunnel of 5 vents of 5' x 5' of Bangalore-Bellary Road.

Sl. No.	Items of work	Per	Quantity	Rate
				Rs. a. p.
1	Earthwork cutting top earth using old materials and gravel to deviation road and consolidating.	C.yds.	97	
2	Dismantling old masonry and carting debris ...	C.ft.	6,238	
3	Removing old apron and rebuilding in places required	C.yds.	57	
4	Earthwork excavation foundation and forming banks	"	64	
5	Stone jelly concrete in surki mortar foundation ...	C.ft.	1,732	
6	Burnt stone in surki mortar foundation Depth 7' ...	"	2,955	
7	Burnt stone superstructure with lift of 6' ...	"	3,201	
8	Burnt stone slabs 8" to 9" for covering roughly dressed with close joints with lift and lead of 6 miles	S.ft.	770	
9	Burnt stone slabs 6" thick dressed and fixed and lead of 6 miles.	"	939	
10	Burnt stone in surki mortar Δ cut water to piers and lead of 6 miles.	C.ft.	44	
11	Two line dressing to coping slab fixed with mortar.	S.ft.	360	
12	Guard stones top rounded and dressed with fixing...	Each	8	
13	Cement pointing exposed portion	Sqr.	31·02	
14	Forming road-way with gravel carted	C.yds.	65	
15	Metalling the roadway with burnt metal and consolidation.	"	38	
16	Sundry works such as baling water during execution	Lump	sum	
17	Size stone revetment new with jelly backing ...	C.yds.	52	
18	Clearing draft channel	Lump	sum	
19	Stone cap over cut water and piers	Each	8	

H. R. VENKATASUBBA RAO,
Executive Engineer.

KOLAR DIVISION.

Dated 24th January 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 17th February 1930, for restoring Nandamballi Tamatanakunte, R. No. 118—870 of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates, at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and seventy-five in cash or Government Promissory Notes as earnest money and be superscribed "Tender for restoring Nandamballi Tamatanakunte R. No. 118—870 of Kolar Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection or any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. The tenderer must quote specific rates for each item of work both in words and in figures.

10. The tenderer stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.